

**NOTES:**

Dimensional detailed drawings showing layout and description of pumping equipment inside pump station shall be furnished Engineer for approval prior to manufacture or installation of equipment.

Pump equipment which requires fastening to floor or ceiling shall be held secure by use of 'J' Bolts or concrete lag bolts properly installed of a size recommended by pumping equipment manufacture.

See Special Provision for Design and Construction Requirements on pumps and equipment.

