8	N D	VG-1-010(05)	93

SIGN SUMMARY

SIGN SUPPORTS

STATION	LOCATION	SIGN NO. OR ASSEMBLY NO.	SIGN AREA FLAT SHEET SQ. FT.	SIGN AREA PANEL SQ. FT.	POST DIMENSIONS LENGTH 1st	POST DIMENSIONS LENGTH 2nd	POST DIMENSIONS SIZE in.	SLEEVE DIMENSIONS LENGTH 1st	SLEEVE DIMENSIONS LENGTH 2nd	SLEEVE DIMENSIONS SIZE in.	A-FRAME BRACE LENGTH 1st	A-FRAME BRACE LENGTH 2nd	A-FRAME BRACE SIZE	A-FRAME BRACE ATTACHMENT SECTION LENGTH	A-FRAME BRACE ATTACHMENT SECTION SIZE	A-FRAME BRACE ATTACHMENT SECTION NO.	A-FRAME BRACE REINF. SLEEVE LENGTH	A-FRAME BRACE REINF. SLEEVE SIZE	A-FRAME BRACE REINF. SLEEVE NO	ANCHORAGE UNIT POST 1st	ANCHORAGE UNIT POST 2nd	ANCHORAGE UNIT POST SIZE	ANCHORAGE UNIT POST REIN SLEEVE LENGTH	ANCHORAGE UNIT POST REIN SLEEVE SIZE	ANCHORAGE UNIT BRACE 1st	ANCHORAGE UNIT BRACE 2nd	ANCHORAGE UNIT BRACE SIZE	TOTAL SUPPORT WEIGHT LBS.	RESET SIGN PANELS	RESET SIGN SUPPORTS
36+30 Rt.	BUSINESS 10	9 RM	9.19		11.583		2½x2½													4.000		2½x2½	0.500	3x3				48.27		
37+60 Rt.	BUSINESS 10	9 RM	9.19		11.583		2½x2½													4.000		2½x2½	0.500	3x3				48.27		
40+15 Lt.	BUSINESS 10	9 RM	9.19		11.583		2½x2½													4.000		2½x2½	0.500	3x3				48.27		
0+70 Lt.	BUSINESS 10	3 RS	13.25		10.750	10.750	2¼x2¼													4.000	4.000	2¼x2¼	0.500 (2)	3x3				91.93		
0+75 Lt.	BUSINESS 10	3 RS	13.25		10.750	10.750	2¼x2¼													4.000	4.000	2¼x2¼	0.500 (2)	3x3				91.93		
1+00 Lt.	BUSINESS 10	7 RS	1.50		8.750		1½x1½													4.000		1½x1½	0.500	2x2				24.37		
2+60 Rt.	BUSINESS 10	7 RS	1.50		8.750		1½x1½													4.000		1½x1½	0.500	2x2				24.37		
4+40 Lt.	BUSINESS 10	9 RM	9.19		11.583		2½x2½													4.000		2½x2½	0.500	3x3				48.27		
0+70 Lt.	Business 10	R4-7-30	15.00	(Back to Back)																										
0+75 Lt.	Business 10	R5-1-3	6.25	(Back to Back)																										
7+00 Rt.	Business 10	19 WS	6.25		10.250		2½x2½													4.000		2½x2½	0.500	3x3				44.58		
9+10 Lt.	Business 10	47 RS	15.00		10.750	10.750	2½x2½													4.000	4.000	2½x2½	0.500 (2)	3x3				91.93		
9+93 Rt.	Business 10	56 WS	9.25		10.250		2½x2½													4.000		2½x2½	0.500	3x3				44.58		
Grand Total			114.01																									606.77		

TELESCOPING PERFORATED TUBES

TUBE SIZE IN.	WALL THICKNESS IN.	U.S. STANDARD GUAGE	WEIGHT PER FOOT LBS.	MOMENT OF INERTIA IN.4	CROSS SECT. AREA IN. SQ.	SECTION MODULUS IN.3
1 x 1	.105	12	1.070	.026	.210	.052
1¼ x 1¼	.105	12	1.427	.070	.315	.112
1½ x 1½	.105	12	1.705	.129	.380	.172
1¾ x 1¾	.105	12	2.060	.231	.485	.264
2 x 2	.105	12	2.416	.372	.590	.372
2¼ x 2¼	.105	12	2.773	.561	.695	.499
2½ x 2½	.105	12	3.141	.804	.803	.643
3 x 3	.1875		7.178	2.791	2.109	1.861